



CUSTOMER RESPONSIBILITIES:

STEP 1: POUR THE **CONCRETE MONOLITHIC SLAB**.

STEP 2: ANCHOR THE STRUCTURE USING THE SUGGESTED **SIMPSON STRONG-TIE**. ANCHOR TIES SHALL BE SPACED MAXIMUM OF 8FT APART.

